


#### overview

- ◆ Run 2A STT in production now
- additional boards are required for Run 2B
  - existing designs (except for one board)
  - second production run using the same vendors
- fiberoptic hardware for additional channels
  - VTMs, splitters, fibers
- firmware and software modifications
- crates, racks, power supplies do not require modification



- run 2A STT
  - ◆ inputs: 432 axial silicon strip detectors
  - ♦ 6 VME crates each covering 2£30° in f




FRC
STCs
TFCs
per crate



#### • run 2B SMT

layer	Readout units		
	f	Z	total
0	12	12	144
1	12	6	72
2	12	4	48
3	18	4	72
4	24	4	96
5	30	4	120




Run 2A 432 9 STCs/crate

Run 2B 552 12 STCs/crate


w/o layer 4 456 10 STCs/crate



#### run 2B simulations




rejection of events with light quark jets ( $Z \rightarrow qq$ ) versus efficiency for WH( $\rightarrow$ bb) events if one STT track with  $s_b$  > threshold is required






#### run 2B simulations



rejection of fake CFT tracks when a matching STT track with  $p_T > 10$  GeV and at most one missing layer is required







#### cost

Component	quantity	M&S cost	contingency
Motherboard	20	\$38.9k	\$10.3k
ВС	20	\$21.4k	\$5.8k
STC	7	\$22.7k	\$5.9k
VTM	10	\$23.5k	\$11.8k
LTB	52	\$10.7k	\$2.9k
LRB	46	\$13.2k	\$3.5k
TFC	8	\$42.4k	\$11.6k
hotlink repeaters	15	\$13.1k	\$6.6k
Cables	125	\$1.0k	\$0.3k
Splitters	26	\$3.3k	\$1.6k
Fibers	52	\$1.3k	\$0.7k
Engineering		\$38.4k	\$38.4k
Total		\$229.8k	\$99.4k



#### schedule

- ◆ April 2003: Begin ordering parts.
  - do this early to minimize the danger of components becoming obsolete.
- ◆ August 2004: Hardware production starts.
- ◆ December 2004: Hardware production completed.
- ◆ May 2005: Shutdown Installation begins.
- June 2005: Technical commissioning begins.
- ◆ September 2005: ready for beam.



#### high risk items

- firmware updates
  - firmware on STC and possibly other cards will have to be updated to account for any changes in the input and/or algorithms.
  - firmware updates may also be required if redesign is required because parts have become obsolete.
  - → large contingency (100%)

#### VTMs

- 850 nm optical transmission components are about to become obsolete.
- →order extra spares
- → order as soon as possible